

AD-A085 214

WOODWARD-CLYDE CONSULTANTS PLYMOUTH MEETING PA

F/6 13/13

NATIONAL DAM INSPECTION PROGRAM. KNIGHT DAM. (NDS I.D. NUMBER 0--ETC(U)

APR 80 M F BECK, J H FREDERICK

DACW31-80-C-0010

NL

UNCLASSIFIED

1-1-1
2-1-1
3-1-1



END
DATE
FILMED
6 80
DTIC



MICROCOPY RESOLUTION TEST CHART
NATIONAL BUREAU OF STANDARDS 1963-A

ADA085214

WOODWARD-CLYDE CONSULTANTS

DACW31-80-C-0018

4157


DISCLAIMER NOTICE

**THIS DOCUMENT IS BEST QUALITY
PRACTICABLE. THE COPY FURNISHED
TO DTIC CONTAINED A SIGNIFICANT
NUMBER OF PAGES WHICH DO NOT
REPRODUCE LEGIBLY.**

1

⑥ National Dam Inspection PROGRAM.
KNIGHT DAM, PERKIOMEN CREEK, Montgomery County,
PENNSYLVANIA.
(NDS I.D. NO. 00395,
DER I.D. NO. 46-257)
Number
←
PHASE I INSPECTION REPORT,

⑩ Mary F./Beck
John H./Frederick, Jr



DTIC
ELECTE
JUN 6 1980
D
C

⑮ DACW31-80-C-0018

Prepared by:

WOODWARD-CLYDE CONSULTANTS
5120 Butler Pike
Plymouth Meeting, Pennsylvania 19462

Submitted to:

DEPARTMENT OF THE ARMY
Baltimore District, Corps of Engineers
Baltimore, Maryland 21203

⑪ APR 1980

⑫ 86

This document has been approved
for public release and sale; its
classification is unlimited.

394157

Enc

PREFACE

This report is prepared under guidance contained in the Recommended Guidelines for Safety Inspection of Dams for Phase I Investigations. Copies of these guidelines may be obtained from the Office of the Chief of Engineers, Washington, D.C. 20316. The purpose of a Phase I investigation is to expeditiously identify those dams which may pose hazards to human life or property. The assessment of the general condition of the dam is based upon available data and visual inspections. Detailed investigations, testing and detailed computational evaluations are beyond the scope of a Phase I investigation; however, the investigation is intended to identify the need for more detailed studies.

In reviewing this report, it should be realized that the reported condition of the dam is based on observations of field conditions at the time of inspection along with data available to the inspection team. In cases where the reservoir was lowered or drained prior to inspection, such action, while improving the stability and safety of the dam, removes the normal load on the structure and may obscure certain conditions which might otherwise be detectable if inspected under the normal operating environment of the structure.

It is important to note that the condition of a dam depends on numerous and constantly changing internal and external conditions, and is evolutionary in nature. It would be incorrect to assume that the present condition of the dam will continue to represent the condition of the dam at some point in the future. Only through frequent inspections can unsafe conditions be detected, and only through continued care and maintenance can these conditions be prevented or corrected.

Phase I inspections are not intended to provide detailed hydrologic and hydraulic analyses. In accordance with the established Guidelines, the spillway design flood is based on the estimated "Probable Maximum Flood" for the region (greatest reasonably possible storm runoff), or fractions thereof. The spillway design flood provides a measure of relative spillway capacity and serves as an aid in determining the need for more detailed hydrologic and hydraulic studies, considering the size of the dam, its general condition and the downstream damage potential.

Accession For	
NTIS GMAI	<input checked="checked" type="checkbox"/>
DDC TAB	<input type="checkbox"/>
Unannounced	<input type="checkbox"/>
Justification	<i>for file</i>
By	
Distribution	
Available for	
Dist	special
A	23 CP

**PHASE I INSPECTION REPORT
NATIONAL DAM INSPECTION PROGRAM**

Name of Dam: Knight Dam
County Located: Montgomery County
State Located: Pennsylvania
Stream: Perkiomen Creek
Coordinates: Latitude 40° 20.0'
Longitude 75° 28.9'
Date of Inspection: November 19, 1979

Knight Dam is owned by the Montgomery County Commissioners and maintained by the Parks Department. Visual inspection of the exposed sections of the dam and review of the limited available data indicate that Knight Dam is in good condition. It is noted that the entire spillway and apron were submerged and could not be inspected. Therefore, a complete visual assessment of the structure could not be made. The dam is classified as a "Small" size structure with a "High" hazard classification consistent with its potential in the event of sudden failure for extensive property and loss of life downstream along Perkiomen Creek.

In accordance with criteria established by Federal (OCE) Guidelines, the spillway design flood for this "Small" size dam and "High" hazard classification is 0.5 to the full Probable Maximum Flood (PMF). As the total storage capacity is nearer the lower limit for the "Small" size classification and as the weir can be expected to be submerged during the PMF, the selected spillway design flood is 0.5 PMF.

Hydrologic and hydraulic calculations indicate that the spillway structure is capable of discharging about 0.47 PMF without overtopping the spillway walls. As 0.5 PMF is not judged to cause failure of the dam by overtopping, the spillway rating for this structure is considered to be "Inadequate" but not "Seriously Inadequate".

It is recommended that the following items of routine maintenance and surveillance be undertaken as soon as practical.

- (1) The apron area along the downstream toe of the spillway should be periodically inspected, especially after periods of high flows to check for scour or deterioration of the downstream toe.

KNIGHT DAM, NDS I.D. No. 00395

- (2) The trees growing against the left spillway wall should be removed.
- (3) The joint filler at the expansion joints in the spillway walls should be replaced.
- (4) The erosion noted at the downstream end of the left spillway wall is not significant at this time but should be monitored.

Because of the location of the dam and the potential for heavy property damage and possible loss of life in the event of failure, a formal procedure of observation and warning during periods of high precipitation should be developed and implemented. This procedure should include a method of warning downstream residents along Perkiomen Creek that high flows are expected and provisions for evacuating these people in the event of an emergency. An operation and maintenance procedure should also be developed to insure that all pertinent items are carefully inspected on a regular basis and maintained in the best possible condition.

Mary F. Beck


Mary F. Beck, P.E.
Pennsylvania Registration 27442
Woodward-Clyde Consultants

4/30/80

Date

John H. Frederick, Jr.

John H. Frederick, Jr., P.E.
Maryland Registration 7301
Woodward-Clyde Consultants



4/30/80

Date

APPROVED BY:

James W. Peck

JAMES W. PECK
Colonel, Corps of Engineers
District Engineer

21 MAY 80

Date



OVERVIEW
KNIGHT DAM, MONTGOMERY COUNTY, PENNSYLVANIA

TABLE OF CONTENTS

	<u>PAGE</u>
Preface	i
Assessment and Recommendations	ii
Overview Photograph	iv
 SECTION 1 - PROJECT INFORMATION	
1.1 General	1
1.2 Description of Project	1
1.3 Pertinent Data	2
 SECTION 2 - ENGINEERING DATA	
2.1 Design	4
2.2 Construction	4
2.3 Operational Data	4
2.4 Evaluation	4
 SECTION 3 - VISUAL INSPECTION	
3.1 Findings	5
3.2 Evaluation	6
 SECTION 4 - OPERATIONAL PROCEDURES	
4.1 Procedures	8
4.2 Maintenance of the Dam	8
4.3 Maintenance of Operating Facilities	8
4.4 Warning Systems In Effect	8
4.5 Evaluation	8
 SECTION 5 - HYDROLOGY/HYDRAULICS	
5.1 Evaluation of Features	9
 SECTION 6 - STRUCTURAL STABILITY	
6.1 Evaluation of Structural Stability	11
 SECTION 7 - ASSESSMENT/REMEDIAL MEASURES	
7.1 Dam Assessment	12
7.2 Remedial Measures	12
 APPENDIX	
A Visual Inspection	
B Engineering Data, Design, Construction and Operation	
C Photographs	
D Hydrology/Hydraulics	
E Plates	
F Geology	

PHASE I INSPECTION REPORT
NATIONAL DAM INSPECTION PROGRAM
KNIGHT DAM
NATIONAL ID NO. PA 00395
DER NO. 46-257

SECTION 1
PROJECT INFORMATION

1.1 General.

a. Authority. The Dam Inspection Act, Public Law 92-367, authorized the Secretary of the Army, through the Corps of Engineers, to initiate a program of inspection of dams throughout the United States.

b. Purpose. The purpose of the inspection is to determine if the dam constitutes a hazard to human life or property.

1.2 Description of Project.

a. Dam and Appurtenances. Knight Dam is a concrete gravity run-of-the-river dam with an ogee weir about 15 feet above the existing streambed. The 415 foot long, 22 foot high dam impounds a reservoir of about 170 acre-feet at normal pool. The upstream face of the dam is vertical. A 155 foot long concrete retaining wall at the left end of the dam, with a top elevation of 220, prevents water from flowing over Pennsylvania Route 29. An 83 foot long retaining wall is at the right end with the same top elevation. Construction documentation indicates the weir section is founded on rock.

Outlet works are located at the right end of the dam, as shown in Photograph 3, and consist of two conduits which are gated at the upstream end and reported to be 24 inches in diameter. The gate hoists are operated from a platform above the conduits, access to which is through a locked gate.

b. Location. The dam is located across the Perkiomen Creek, about 3,000 feet southwest of the center of Green Lane Borough. The dam is in Upper Frederick and Marlborough Townships, Montgomery County, Pennsylvania. The dam site and reservoir are located on the USGS Quadrangle map entitled "Perkiomenville, Pennsylvania", at coordinates N 40° 20.0' W 75° 28.9'. A regional location plan of Knight Dam and reservoir is enclosed as Plate 1, Appendix E.

c. Size Classification. The dam is classified as a "Small" size dam by virtue of its estimated total capacity of 479 acre-feet and 22 foot height.

d. Hazard Classification. A "High" hazard classification is assigned consistent with the dam's location above an urban area and the potential to cause extensive property damage and possible loss of life downstream along the creek.

e. Ownership. The dam is owned by the Montgomery County Commissioners. All correspondence should be addressed to Mr. A. Russell Parkhouse, Chairman, Montgomery County Commissioners, Court House, Norristown, Pennsylvania 19401.

f. Purpose of Dam. The dam serves to prevent flooding of the adjacent highway, Pennsylvania Route 29, and the reservoir is used for recreational purposes.

g. Design and Construction History. The original dam at the site, Knickerbocker Dam, was one of three dams built around 1888 by the American Ice Company of Philadelphia. The rockfill timber crib structure was about 12 feet high and 250 feet long. During the flood of 1902, all dams were breached, increasing the water level at Brey Dam, 3,500 feet downstream, by three feet. The dam, or what remained of it, was at the site when construction of the present Knight Dam began.

Drawings for Knight Dam were prepared by the office of the Montgomery County Engineer in 1957 and 1958. The original plans were for a longer dam with the outlet works near the center, rather than at the right abutment. Except for a drawing which shows the dates when portions of the concrete weir and retaining walls were cast, there are no drawings in the state files which show the as-built configuration of the dam with the outlet works at the right abutment. Construction records indicate that concrete for the weir and retaining walls was cast between February 8 and September 1, 1960, when one section of spillway was remaining to be cast. No other design and construction history was available in Department of Environmental Resources files.

h. Normal Operating Procedures. Reservoir flows are normally discharged over the weir.

1.3 Pertinent Data.

A summary of pertinent data for Knight Dam is presented as follows.

a.	Drainage Area (square miles)	94.5
b.	Discharge at Dam Site (cfs)	
	Maximum Known Flood at Dam Site (June 1972)	11,400 ⁽¹⁾
	At Top of Dam	30,500
c.	Elevation (feet above MSL)	
	Top of Dam	220.0
	Spillway Weir	213.0
	Pond Drain Inlet	201±
	Pond Drain Outlet	201±
	Tailwater (November 19, 1979)	201.8
	Stream Bed at Downstream Toe	197.6
d.	Reservoir (feet)	
	Length at Normal Pool (est)	3,500
	Length at Maximum Pool (est)	5,000
	Fetch at Normal Pool	1,300
e.	Estimated Storage (acre-feet)	
	To Spillway	170
	To Top of Dam	479
f.	Reservoir Surface Area (acres)	
	Normal Pool	34
g.	Dam Data	
	Type	Concrete gravity
	Length	415 feet
	Maximum Height	22 feet
	Volume	5,900 cubic yards
	Side Slopes	
	Upstream	Vertical
	Downstream	Ogee weir
	Cutoff	None known
	Grout Curtain	None
h.	Spillway	
	Type	Ogee weir
	Elevations (feet)	
	Weir	213.0
	Downstream Apron	197.6
i.	Outlet Works	
	Type	Two 24 inch conduits gated at upstream end
	Reservoir Drain Inlet	201±
	Conduit Outlet Invert	201±

(1) Reported maximum discharge at upstream Green Lane Dam.

SECTION 2 ENGINEERING DATA

2.1 Design.

a. Data Available. The data available for review from Department of Environmental Resources (DER) files were limited to design drawings for a somewhat different dam at the site (with the outlet works at the center of the dam and a footbridge crossing the dam), test boring logs and a concrete placement record sheet. The only engineering analysis available for this dam is a stability analysis for the weir section. The Montgomery County Engineer's Office provided the drawing enclosed as Plate 4, Appendix E.

b. Design Features. The principal design features of Knight Dam are illustrated on the plan and cross-section enclosed as Plates 2 and 3, Appendix E. Data for these plates were obtained from DER files.

2.2 Construction.

Beyond the limited information given in Section 1.2, there are no data available concerning the construction history of this dam and reservoir.

2.3 Operational Data.

There are no operational records maintained. There are no known minimum flow requirements downstream of this dam.

2.4 Evaluation.

a. Availability. Information presented herein was obtained from records located in DER files in Harrisburg, Pennsylvania, and the Montgomery County Engineer's Office and from conversations with the Owner's representative.

b. Adequacy. The available data included in the state files are not adequate to evaluate the engineering aspects of the dam and appurtenant structures.

c. Validity. There is no reason to question the validity of the limited available data.

SECTION 3 VISUAL INSPECTION

3.1 Findings.

a. General. Observations and comments of the field inspection team are contained in the checklist enclosed herein as Appendix A, and are summarized and evaluated in the following subsections. In general, the appearance of the facility in November 1979, indicates that the dam is in good condition. At the time of the inspection, the creek was flowing at a normal rate over the spillway and, thus, the ogee section and downstream apron could not be inspected. A plan and cross-section of the dam are shown in Plates 2 and 3, Appendix E.

b. Dam. The vertical alignment of the dam was checked, and the profile is shown on sheet 5B, Appendix A. No discernible horizontal or vertical displacement was noted along the crest. Water was flowing uniformly over the entire length of the dam. The junction to the right abutment appears in good condition. The minimum elevation of backfill behind the right spillway wall is equal to the top of the spillway wall. The wall itself is in good condition, with no cracking noted, although some joint filler is missing from expansion joints in the wall. Drains through the wall were rust stained. The left spillway wall also appears in good condition. The left spillway wall, shown in Photograph 6, is not backfilled to the top at its downstream end. The wall extends 105 feet upstream into natural ground. Two small trees are growing adjacent to the wall on the reservoir side near the upstream end. These should be removed. On the highway side of the wall near the downstream end are two minor depressions. At the downstream end of the wall is erosion resulting from surface runoff or foot traffic. Large stone is at the downstream end of the wall. The depressions and erosion are not considered significant at this time but should be monitored. The exposed portion of the wall has fine vertical cracks extending two to three feet below the top of the wall, spaced uniformly between construction joints. Some of the vertical cracks are connected at the bottom by a horizontal crack. This cracking is assessed to be temperature cracking and not structural cracking. Joint filler is completely missing from construction joints in the wall and should be replaced.

Outlet works consist of two conduits, reported to be 24 inches in diameter, through the dam at the right end, as shown in Photograph 2. Both conduits are gated at their

upstream end, and gate hoists are located on the platform above them, shown in Photograph 3. The platform appears to be in good condition. Both gates were operated smoothly and appeared to seat completely. Unauthorized access is prevented by a locked gate through a cyclone and barbed wire fence on the top of the right retaining wall.

c. Reservoir. The reservoir slopes are flat to moderate and vegetated to the water's edge with grass or trees. Knight Dam was built immediately downstream of the confluence of Deep Creek with Perkiomen Creek. Immediately above this confluence on Deep Creek is Deep Creek Dam. Knight Dam reservoir extends up to the toe of Deep Creek Dam, which is shown on Photograph 10. About 3,000 feet due north of Knight Dam on Perkiomen Creek is Green Lane Dam. This 87 foot high dam is shown on Photograph 9. No sedimentation was noted at the upper end of the reservoir, and very little debris was noted.

d. Downstream Channel. The downstream channel is the Perkiomen Creek, as shown in Photograph 4. The stream narrows from the 400 foot width at the dam to about 100 feet under the first highway bridge, about 300 feet downstream. Below the first highway bridge, the channel is about 100 feet wide and up to six feet deep. There is a small run-of-the-river dam about 1,000 feet below Knight Dam, which is about five feet high and 120 feet long. Brey Dam, eight feet high and about 3,500 feet below Knight Dam, is immediately downstream of the first major damage center. Upstream of Brey Dam is an old mill building, shown in Photograph 8, which still has a mill race diverting flow from the Perkiomen Creek into the building. Water flows through the mill building and under Route 29 before entering a channel and being carried back into the Perkiomen Creek. There is at least one apartment on its upper floors. Upstream of the mill building are seven homes, some of which are shown in Photograph 7. Three of the houses appear to be less than six feet above the creek bank. All along the Perkiomen Creek to its confluence with the Schuylkill River are scattered houses and businesses built in the floodplain.

3.2 Evaluation.

Inspection of the dam, outlet works and retaining walls disclosed no evidence of apparent past or present movement that would indicate existing instability of the dam, spillway walls or outlet structure. The dam crest appears to be uniform and water flows smoothly over it. Since flow was passing over the spillway at the time of the inspection, the

toe of the spillway could not be inspected for undermining, scour or the condition of the apron section. All exposed structural features of the dam were observed to be in good condition.

The only items to be noted are of a routine maintenance nature, and they are the replacement of joint filler material in both the left and right spillway walls and removal of trees adjacent to the left spillway wall. The erosion noted at the downstream end of the left spillway wall requires only monitoring at this time.

SECTION 4 OPERATIONAL PROCEDURES

4.1 Procedures.

Operation of the dam does not require a dam tender. Under normal conditions, the pond drain gates are closed, and water discharges over the dam.

4.2 Maintenance of the Dam.

Upper Perkiomen Valley Park employees provide routine maintenance for the dam.

4.3 Maintenance of Operating Facilities.

Park employees provide routine maintenance to the operating facilities. The pond drain sluice gate is operated in the spring.

4.4 Warning Systems In Effect.

There is no written warning system in effect for this dam.

4.5 Evaluation.

It is judged that the current operating procedure, which does not require a dam tender, is a realistic means of operating the relatively simple control facilities of Knight Dam. It is noted that formal operational, maintenance and warning procedures should be developed and implemented. Maintenance procedures should include an inspection checklist which would include a listing of items to be checked during each inspection and repaired as necessary to insure proper performance of the structure.

SECTION 5 HYDROLOGY/HYDRAULICS

5.1 Evaluation of Features.

a. Design Data. There is no original design data nor subsequent hydrologic/hydraulic evaluation data available for this dam. The stability analysis indicates a "full head" elevation on the weir to be 219. The watershed is composed of three major subwatersheds. About 600 feet west of Knight Dam is Deep Creek Dam and watershed, which has a total drainage area of 5.62 square miles. The Deep Creek Watershed is approximately 70 percent wooded and 30 percent residential development. About 1.1 river miles upstream of Knight Dam is Green Lane Dam, with a drainage area of 71 square miles. Green Lane Dam is 87 feet high and 780 feet long, and the top of the dam impounds a maximum pool of over 25,000 acre-feet. About 0.6 river mile upstream of Knight Dam is the confluence of Perkiomen Creek and Macoby Creek. Macoby Creek has a drainage area of about 18 square miles. There are no dams located within that sub-watershed. Elevations within the entire 94.5 square mile Knight Dam drainage area range from about 1,100 in the upper reaches to 213, the elevation of Knight Dam.

In accordance with criteria established by Federal (OCE) Guidelines, the spillway design flood for this "Small" size dam and "High" hazard classification is one-half to the full Probable Maximum Flood (PMF). As the total storage capacity is nearer the lower limit for the "Small" size classification and as the weir can be expected to be submerged during the PMF, the selected spillway design flood is the 0.5 PMF.

b. Experience Data. There are no records of reservoir levels kept for this dam, and there is no estimate of the maximum depth of water over the dam. It is reported that the maximum discharge of the upstream Green Lane Dam was 11,400 cfs in June 1972, during Tropical Storm Agnes.

c. Visual Observations. On the date of the inspection, there were no conditions observed that would indicate a reduction in spillway capacity during an extreme event. Observations regarding the condition of the downstream channel, spillway and reservoir are located in Appendix A and are discussed in greater detail in Section 3.

d. Overtopping Potential. The overtopping potential of this dam was estimated using the HEC-1, Dam Safety Version, computer program. A brief description of the program is included in Appendix D.

Calculations for this investigation estimate a spillway discharge of about 30,500 cfs when the reservoir level is at the elevation of the spillway walls. The HEC-1 program computed the peak 0.5 PMF inflow to be about 32,614 cfs, and the program estimates the spillway walls would be overtopped by 0.3 foot during the 0.5 PMF. The spillway is capable of passing about 0.47 PMF without overtopping the walls. Failure of upstream Deep Creek Dam was considered and is expected not to increase the peak discharge from Knight Dam.

e. Spillway Adequacy. A spillway that will not pass the 0.5 PMF without overtopping the dam is rated as "Seriously Inadequate", provided two other conditions are present. One is failure of the dam by overtopping. The dam is judged not to fail during the 0.5 PMF, and therefore, the spillway is rated as "Inadequate" but not "Seriously Inadequate".

f. Downstream Conditions. The first damage center is about 1,800 feet below the dam where a house is built in the floodplain. A major downstream damage center is approximately 3,100 feet below the dam, above the intersection of Route 29 and Perkiomenville Road, as shown on Plate 1. At that point, three of the seven (all of which are not shown on Plate 1) houses are less than six feet above the bank of the Perkiomen Creek. The structure closest to Brey Dam, shown on Plate 1, is an old mill. Water is still diverted from Perkiomen Creek through the building. All along the Perkiomen Creek to its confluence with the Schuylkill River are scattered homes and businesses built in the floodplain.

SECTION 6 STRUCTURAL STABILITY

6.1 Evaluation of Structural Stability.

a. Visual Observations. Visual observations detected no evidence of existing or impending instability of the structure. All exposed items of the structure were inspected and found to be in good condition. There was no distortion along the spillway crest to infer excessive scour downstream, monolithic displacement or structural deterioration of the ogee section. However, the entire ogee section was covered with water and could not be thoroughly inspected. The nonoverflow sections of the dam were found to be in good condition.

b. Design and Construction Data. Known design and construction documentation is described in Section 1.2. Included as part of the drawings dated 1957 and 1958 for a proposed dam at the site is a stability analysis of the weir section. The design analysis indicated that the spillway stability is adequate. The spillway which was constructed, as shown on Plate 3, extends ten feet deeper than the original design. Based on the original analysis, it is assessed that the stability of the as-built weir is also adequate.

c. Operating Records. There are no operational records for this structure.

d. Post-Construction Changes. There is no evidence to suggest that modifications were made to this dam since it was completed in 1960.

e. Seismic Stability. The dam is located in Seismic Zone 1. Normally it can be considered that if a dam in this zone is stable under static loading conditions, it can be assumed safe for any expected earthquake conditions. As the dam is qualitatively assessed to be stable under present static loading conditions, it can reasonably be assumed to be stable under seismic loading conditions.

SECTION 7 ASSESSMENT/REMEDIAL MEASURES

7.1 Dam Assessment.

a. Evaluation. Visual inspection of the exposed sections of the dam and review of the very limited available data indicate that Knight Dam is in good condition. It is noted that the entire spillway and apron were submerged and could not be inspected. Therefore, a complete assessment of the structure could not be performed. In accordance with criteria established by Federal (OCE) Guidelines, the spillway design flood for this "Small" size dam and "High" hazard classification is one-half to the full Probable Maximum Flood (PMF). As the total storage capacity is nearer the lower limit for the "Small" size classification and as the weir can be expected to be submerged during the PMF, the selected spillway design flood is one-half the PMF. Calculations presented in Appendix D indicate that the spillway is capable of discharging about 0.47 PMF without overtopping the spillway walls. As the 0.5 PMF is not judged to cause failure, the spillway rating for this structure is considered to be "Inadequate" but not "Seriously Inadequate".

b. Adequacy of Information. Information available for this investigation was sufficient to evaluate the dam and appurtenant structures in accordance with Phase I Inspection criteria. However, an insufficient portion of the structure was exposed to perform a complete visual inspection.

c. Urgency. The recommendations presented in Section 7.2 should be implemented as specified.

7.2 Remedial Measures.

a. Facilities. It is recommended that the following items of routine maintenance and surveillance be undertaken as soon as practical.

- (1) The apron area along the downstream toe of the spillway should be periodically inspected, especially after periods of high flows to check for scour or deterioration of the downstream toe.
- (2) The trees growing against the left spillway wall should be removed.

- (3) The joint filler at the expansion joints in the spillway walls should be replaced.
- (4) The erosion noted at the downstream end of the left spillway wall is not significant at this time but should be monitored.

b. Operation and Maintenance Procedures. Because of the location of the dam and the potential for heavy property damage and possible loss of life in the event of failure, a formal procedure of observation and warning during periods of high precipitation should be developed and implemented. This procedure should include a method of warning downstream residents along Perkiomen Creek that high flows are expected and provisions for evacuating these people in the event of an emergency. An operation and maintenance procedure should also be developed to insure that all pertinent items are carefully inspected on a regular basis and maintained in the best possible condition.

APPENDIX

A

CHECK LIST
VISUAL INSPECTION
PHASE I

Sheet 1 of 11

Name Dam Knight Dam County Montgomery State Pennsylvania National ID # PA 00395
Type of Dam Concrete Hazard Category High
Date(s) Inspection 11/19/1979 Weather Sunny Temperature 60's

Pool Elevation at Time of Inspection 213.2 M.S.L. Tailwater at Time of Inspection 201.8 M.S.L.

Inspection Personnel:

Mary F. Beck (Hydrologist) Vincent McKeever (Hydrologist)
(Geotech- (9/13/1979))
Arthur H. Dvinoff nical/Civil) John H. Frederick
(4/9/1980)
Raymond S. Lambert (Geologist)

Mary F. Beck Recorder

Remarks:

Mr. Otto Quinke, Upper Perkiomen Valley Superintendent and park employees were on site
and provided assistance to the inspection team.

CONCRETE/MASONRY DAMS

Sheet 2 of 11

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
-----------------------	--------------	----------------------------

ANY NOTICEABLE SEEPAGE

None observed, the entire downstream toe is under water.

STRUCTURE TO
ABUTMENT/EMBANKMENT
JUNCTIONS

Junction to right abutment appears in good condition. Junction to left abutment appears in good condition with the exception of erosion at the end of the downstream wall caused by surface runoff and/or foot traffic.

DRAINS

Drains through downstream right spillway wall were wet with rust stains.

WATER PASSAGES

N/A

FOUNDATION

Reportedly on firm bedrock.

CONCRETE/MASONRY DAMS

Sheet 3 of 11

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
SURFACE CRACKS CONCRETE SURFACES	No cracking was observed on the right spillway wall which is backfilled to the top of the wall. The left spillway wall which is not backfilled has fine vertical cracks extending 2 to 3 feet below the top of the wall spaced uniformly between expansion joints. Some of the vertical cracks are connected at the bottom by a horizontal crack.	
STRUCTURAL CRACKING	None observed.	
VERTICAL AND HORIZONTAL ALIGNMENT	Both the vertical and horizontal alignment appear to be good.	
MOROLITH JOINTS	None observed, water flowing over weir.	
CONSTRUCTION JOINTS	The joint filler is completely missing from expansion joints in the left spillway wall and partially missing from expansion joints in the right spillway wall.	

EMBANKMENT

Sheet 4 of 11

<u>VISUAL EXAMINATION OF</u>	<u>OBSERVATIONS</u>	<u>REMARKS OR RECOMMENDATIONS</u>
SURFACE CRACKS	N/A	
UNUSUAL MOVEMENT OR CRACKING AT OR BEYOND THE TOE	N/A	
SLOUGHING OR EROSION OF EMBANKMENT AND ABUTMENT SLOPES	N/A	
VERTICAL AND HORIZONTAL ALIGNMENT OF THE CREST	N/A	
RIPRAP FAILURES	N/A	

EMBANKMENT

Sheet 5 of 11

<u>VISUAL EXAMINATION OF</u>	<u>OBSERVATIONS</u>	<u>REMARKS OR RECOMMENDATIONS</u>
------------------------------	---------------------	-----------------------------------

JUNCTION OF EMBANKMENT AND ABUTMENT, SPILLWAY AND DAM		
---	--	--

N/A

ANY NOTICEABLE SEEPAGE		
------------------------	--	--


N/A

STAFF GAGE AND RECORDER		
-------------------------	--	--


N/A

DRAINS		
--------	--	--

N/A




SCALE IN FEET



FIELD OBSERVATION PLAN
KNIGHT DAM

SHEET 5A OF 11



LOOKING UPSTREAM

SCALE IN FEET



**FIELD OBSERVATION PROFILE
KNIGHT DAM**

SHEET 5B OF 11

OUTLET WORKS

Sheet 6 of 11

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
CRACKING AND SPALLING OF CONCRETE SURFACES IN OUTLET CONDUIT	Conduits through dam are located under the right end of the ogee weir. Reported dimensions are 24 inch diameter.	
INTAKE STRUCTURE	Appears in good condition.	
OUTLET STRUCTURE	None, the pipes outlet at the toe of the weir, see Photograph No. 2. Appendix D.	
OUTLET CHANNEL	Discharge is directly into channel below weir.	
EMERGENCY GATE	Both gates operated smoothly and appear to seat completely.	

UNGATED SPILLWAY

Sheet 7 of 11

<u>VISUAL EXAMINATION OF</u>	<u>OBSERVATIONS</u>	<u>REMARKS OR RECOMMENDATIONS</u>
CONCRETE WEIR	At the time of inspection, water was flowing over the crest uniformly.	
APPROACH CHANNEL	N/A	
DISCHARGE CHANNEL	The channel narrows to about 100 feet wide below the dam.	
BRIDGE AND PIERS	None	

GATED SPILLWAY

Sheet 8 of 11

<u>VISUAL EXAMINATION OF</u>	<u>OBSERVATIONS</u>	<u>REMARKS OR RECOMMENDATIONS</u>
CONCRETE SILL	N/A	
APPROACH CHANNEL	N/A	
DISCHARGE CHANNEL	N/A	
BRIDGE AND PIERS	N/A	
GATES AND OPERATION EQUIPMENT	N/A	

INSTRUMENTATION

Sheet 9 of 11

REMARKS OR RECOMMENDATIONS

OBSERVATIONS

VISUAL EXAMINATION

MONUMENTATION/SURVEYS

None

OBSERVATION WELLS

None

WEIRS

None

PIEZOMETERS

None

OTHER

RESERVOIR

Sheet 10 of 11

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
-----------------------	--------------	----------------------------

SLOPES

The reservoir slopes are flat and well vegetated to the water's edge with grass and trees.

SEDIMENTATION

*Little sediment noted at upper end, no effect on flood water storage.
Little debris along reservoir's edge.*

DOWNSTREAM CHANNEL

Sheet 11 of 11

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
CONDITION (OBSTRUCTIONS, DEBRIS, ETC.)	The 100 foot wide downstream channel appears in good condition. Immediately downstream of the dam where the channel narrows from 400 feet, there is some bank cutting which presents no problem. The stream bed contains many large boulders which have resulted from in place weathering of bedrock. About 1,000 feet downstream is a weir about 5 feet high built across the creek.	

SLOPES

The valley gradient is approximately 0.016.

APPROXIMATE NO.
OF HOMES AND
POPULATION

About 0.7 mile below the dam are seven houses an old mill with at least one apartment on its upper floors. Part of the flow from Perkiomen Creek still flows through the race under the mill building. The first floor of at least three of the houses appear to be less than 6 feet above the creek bank. All along Perkiomen Creek are homes built in the flood plain.

APPENDIX

B

NAME OF DAM Knight Dam
 ID # PA 00395

Sheet 1 of 4

CHECK LIST
 ENGINEERING DATA
 DESIGN, CONSTRUCTION, OPERATION
 PHASE I

REMARKS
None available.

ITEM

AS-BUILT DRAWINGS

REGIONAL VICINITY MAP

See Plate 1, Appendix E.

CONSTRUCTION HISTORY

See text, Section 1.2

TYPICAL SECTIONS OF DAM

See Appendix E.

OUTLETS - PLAN

DETAILS

CONSTRAINTS

DISCHARGE RATINGS

RAINFALL/RESERVOIR RECORDS

See Appendix E.

See Appendix D.

None

ITEM	REMARKS
DESIGN REPORTS	None available.
GEOLOGY REPORTS	See Appendix F.
DESIGN COMPUTATIONS HYDROLOGY & HYDRAULICS DAM STABILITY SEEPAGE STUDIES	Only stability calculations available.
MATERIALS INVESTIGATIONS BORING RECORDS LABORATORY FIELD	Unknown See Appendix E. Unknown
POST-CONSTRUCTION SURVEYS OF DAM	None known.
BORROW SOURCES	N/A


ITEM	REMARKS
MONITORING SYSTEMS	None
MODIFICATIONS	None
HIGH POOL RECORDS	None
POST CONSTRUCTION ENGINEERING STUDIES AND REPORTS	None
PRIOR ACCIDENTS OR FAILURE OF DAM DESCRIPTION REPORTS	None
MAINTENANCE OPERATION RECORDS	None

ITEM	REMARKS
SPILLWAY PLAN	See Appendix E.
SECTIONS DETAILS	
OPERATING EQUIPMENT PLANS & DETAILS	None

APPENDIX

C


PHOTOGRAPH LOCATION PLAN
KNIGHT DAM
PLATE C-1





SPILLWAY CREST. NOTE FLOW IS
UNIFORM OVER CREST.

PHOTOGRAPH NO. 1



OUTLET WORKS AT RIGHT END
OF WEIR.

PHOTOGRAPH NO. 2



GATE HOIST AND PLATFORM.

PHOTOGRAPH NO. 3



VIEW OF DOWNSTREAM CHANNEL AND
BRIDGE LOCATED ABOUT 300 FEET
BELOW DAM.

PHOTOGRAPH NO. 4



VIEW OF LEFT SPILLWAY WALL. WEIR
TO RIGHT.

PHOTOGRAPH NO. 5




LEFT UPSTREAM SPILLWAY WALL.

PHOTOGRAPH NO. 6



DOWNSTREAM DAMAGE CENTER LOCATED
ABOUT 0.7 MILE DOWNSTREAM.

PHOTOGRAPH NO. 7




SMALL PART OF PERKIOMEN
CREEK FLOW IS DIVERTED
THROUGH THE BASEMENT OF
THIS BUILDING.

PHOTOGRAPH NO. 8



UPSTREAM GREEN LANE DAM.

PHOTOGRAPH NO. 9



UPSTREAM DEEP CREEK DAM.

PHOTOGRAPH NO. 10

APPENDIX

D

KNIGHT DAM
CHECK LIST
HYDROLOGIC AND HYDRAULIC
ENGINEERING DATA

DRAINAGE AREA CHARACTERISTICS: About 50% wooded, the rest is predominantly open/
farm land, little residential development.

ELEVATION TOP NORMAL POOL (STORAGE CAPACITY): 213.0 feet (170 Acre-Feet).

ELEVATION TOP FLOOD CONTROL POOL (STORAGE CAPACITY): 220.0 feet (479 Acre-Feet).

ELEVATION MAXIMUM DESIGN POOL: 219.0 feet

ELEVATION TOP DAM: 220.0 feet

SPILLWAY

a. Elevation 213.0 feet.

b. Type Concrete ogee weir

c. Width 413.5 feet

d. Length ---

e. Location Spillover Run-of-the-river.

f. Number and Type of Gates None

OUTLET WORKS:

a. Type 2-24 inch conduits.

b. Location Right end.

c. Entrance inverts 201± feet.

d. Exit inverts 201± feet.

e. Emergency draindown facilities Outlet works.

HYDROMETEOROLOGICAL GAGES:

a. Type None maintained by Owner.

b. Location N/A

c. Records N/A

MAXIMUM NON-DAMAGING DISCHARGE: Not determined.

KNIGHT DAM
HYDROLOGIC AND HYDRAULIC
BASE DATA

Sheet 2 of 11

DRAINAGE AREA: (1) 94.5 square miles total.

PROBABLE MAXIMUM PRECIPITATION (PMP)
FOR 10 SQ. MILES IN 24 HOURS: (2) 23.0 inches.

ADJUSTMENT FACTORS FOR DRAINAGE AREA (%): (3)

Zone	<u>6</u>
6 Hours	<u>90</u>
12 Hours	<u>99</u>
24 Hours	<u>109</u>
48 Hours	<u>122</u>

SNYDER HYDROGRAPH PARAMETERS: (4)

Zone	<u>*</u>			
C_p, C_t	<u>0.625, 2.0</u>	Deep Creek (5.62 sq. mile)	Green Lane (71.0 sq. mile)	Macoby Creek (17.93)
L (5)		<u>3.98</u>	<u>18.2</u>	<u>9.75</u>
Lca (6)		<u>2.08</u>	<u>10.4</u>	<u>4.64</u>
$tp = C_t (L \cdot Lca)^{0.3}$		<u>3.77</u>	<u>9.64</u>	<u>6.27</u>

SPILLWAY CAPACITY AT MAXIMUM
WATER LEVEL (7) 30449 cfs

- (1) Measured from USGS maps.
- (2) Hydrometeorological Report No. 33, Figure 1.
- (3) Hydrometeorological Report No. 33, Figure 2.
- (4) Information received from Corps of Engineers, Baltimore District.
- (5) Length of longest water course from outlet to basin divide, measured from USGS maps.
- (6) Length of water course from outlet to point opposite the centroid of drainage area, (see Plate 1, Appendix E) measured from USGS maps.
- (7) See Sheet 4, 11 of this Appendix.

* Parameter determined from analysis of flood records at downstream Gratersford gaging station on Perkiomen Creek. Calculations by Philadelphia Suburban Water Company are dated 1950-53 and were used in the design of upstream Green Lane Dam. In 1973, the original analysis was reviewed by Woodward-Clyde Consultants and judged adequate.

HEC-1, REVISED
FLOOD HYDROGRAPH PACKAGE

The original "Flood Hydrograph Package" (HEC-1), developed by the Hydrologic Engineering Center, Corps of Engineers, has been modified for use under the National Dam Inspection Program. The "Flood Hydrograph Package (HEC-1), Dam Safety Version", hereinafter referred to as, HEC-1, Rev., has been modified to require less detailed input and to include a dam breach analysis. The required input is obtained from the field inspection of a dam, any available design/evaluation data, relatively simple hydraulic calculations, or information from the USGS Quadrangle maps. The input format is flexible in order to reflect any unique characteristics of an individual dam.

HEC-1, Rev. computes a reservoir inflow hydrograph based on individual watershed characteristics such as: area, percentage of impervious surface area, watershed shape, and hydrograph characteristics determined from regional correlation studies by the Corps of Engineers, Baltimore District. The inflow is routed through the reservoir using spillway discharge data obtained from the field inspection or design data. Flood storage capacity is determined from USGS maps or design information and verified by the field inspection. In the event a spillway cannot discharge 0.5 PMF without overtopping and failure of the dam, downstream channel characteristics obtained from the field inspection and USGS maps are input and flows are routed downstream to the damage center and a dam breach analysis is performed.

Included in this Appendix are the HEC-1, Rev. pertinent input values and a summary print-out tables.

BY MFB DATE 4/14/80
 CHKD. BY AHD DATE 4/15/80

SUBJECT Knight Dam
Hydrology/Hydraulics

SHEET 4 OF 11
 JOB No. _____

Classification (Ref. Recommended Guidelines for Safety Inspection of Dams)

1. The hazard classification is rated as "High" as there would be economic loss and possible loss of life in the event of sudden failure.
2. The size classification is "Small" based on its total capacity of 479 Ac-Ft.
3. The selected spillway design flood, based on size and hazard classification, is 0.5 PMF (Probable Maximum Flood).

Hydrology and Hydraulic Analysis

1. Original design data is limited to a stability analysis indicating the full head on the weir to be 219.0, i.e. the design head on the weir is 6.0 ft.

2. Evaluation Data

Inflow hydrograph parameters are shown on sheet 2.

Elevation-storage data. Surface areas for elevations 204, 209, 213 & 218 were measured from a topo plan dated Nov. 1957 (as received by DRR). Surface area for elev. 220 was measured from current USGS map. Area above 220 was estimated.

Elevation-discharge data. Shape of agee section conforms to design head, H_o , of 6.0 ft. The angle of the left spillway wall reduces the effective length of the weir. Assume $L = 410$ ft. $H_o = 6$ ft, $P = 11.5$ ft.

$P/H_o = 11.5/6 = 1.92$ $C_o = 3.93$ Design of Small Dams.

Bureau of Reclamation, 2nd, 1978

W.S.	H_o	H_o/H_o	C_o	C	L	$Q = C L H_o^{3/2}$
213	0	0			410	0
214	1	0.17	0.85	3.34		1369 cfs
215	2	0.33	0.89	3.50		4059 ✓
216	3	0.50	0.92	3.62		7712 ✓ Discharge
217	4	0.67	0.95	3.73		12238 ✓ assuming
218	5	0.83	0.98	3.85		17648 ✓ weir not
220	7	1.17	1.02	4.01		30449 ✓ submerged
222	9	1.50	1.06	4.17		46162 ✓
225	12	2.0	1.07	4.21		71753 ✓

BY MEB DATE 4/15/80

SUBJECT

SHEET 5 OF 11

CHKD. BY _____ DATE _____

Knight Dam

JOB No _____

Hydrology / Hydraulics

Available for review was the preliminary HEC-2 (Water Surface Profiles) run of Perkovich Creek prepared for the Federal Emergency Management Agency. Water surface elevations for a section 70 ft downstream of the dam are:

W.S.	0	
200 ft	0	channel invert
204.6	7,000 cfs	
207.0	12,150	
208.5	15,650	
213.7	29,100 cfs	

Although the weir is partly submerged during 0.5 PMF event, the maximum water level is not expected to be significantly higher. Maximum water elevation during the PMF will be significantly higher.

3. Spillway Adequacy-

A spillway is considered "Seriously Inadequate" only if overtopping by 0.5 PMF will cause failure. As the spillway walls are overtopped without failing by the 0.5 PMF, the spillway is considered "Inadequate".

4. Failure of Upstream Dams

Failure of only upstream Deep Creek Dam was considered. The peak discharge from Deep Creek Dam occurs over 5 hours before the peak discharge from Knight Dam. Thus, Knight Dam peak discharge is not increased, see sheet 11A.

PREVIEW OF SEQUENCE OF STREAM NETWORK CALCULATIONS

RUNOFF HYDROGRAPH AT	GLIN	Green Lane
ROUTE HYDROGRAPH TO	BLU	
RUNOFF HYDROGRAPH AT	IN	Deep Creek
ROUTE HYDROGRAPH TO	OUT	
RUNOFF HYDROGRAPH AT	KCI	Macoby Creek
COMBINE 3 HYDROGRAPHS AT	KIN	Knight Dam
ROUTE HYDROGRAPH TO	KNOBT	
END OF NETWORK		

 FLOOD HYDROGRAPH PACKAGE (HEC-1)
 DAM SAFETY VERSION JULY 1970
 LAST MODIFICATION 26 FEB 79

RUN DATE= 80/04/15.
 TIME= 05.46.52.

KNIGHT DAM
 NAT ID NO. FA 935 DER NO. 46-257
 OVERTOPPING ANALYSIS

JOB SPECIFICATION											
NO	NHR	NMIN	IDAY	IRR	IMIN	METRC	IPLT	IPRT	NSTAR		
300	1	0	0	0	0	0	0	-4	0		
			JOPER	NUT	LROPT	IRACE					
			5	0	0	0					

MULTI-PLAN ANALYSES TO BE PERFORMED
 NPLAN= 1 NRTIU= 3 LRTO= 1
 RTIOS= .40 .50 1.00

SUB-AREA RUNOFF COMPUTATION

GREEN LANE INFLU HYDROGRAPH

ISTAG	ICOMP	IECON	ITAPE	JPLT	JPRI	INAME	ISTAGE	IAUTO
BLIN	0	0	0	0	0	1	0	0

HYDROGRAPH DATA

INDB	IUNG	TAREA	SNAP	IRSDA	TRSPC	RAT10	ISROW	ISAME	LOCAL
1	1	71.00	0.00	75.00	0.00	0.000	0	1	0

PRECIP DATA

SPFE	PNS	RA	R12	R24	R48	R72	R96
0.00	23.00	90.00	99.00	109.00	122.00	0.00	0.00

IRSPC COMPUTED BY THE PROGRAM IS .846

LOSS DATA

LROPT	STRKR	DLTKR	RIOL	ERAIN	STRKS	RTION	STRTL	CNSTL	ALSMX	RTIMP
0	0.00	0.00	1.00	0.00	0.00	1.00	1.00	.05	0.00	0.00

UNIT HYDROGRAPH DATA

TP= 9.64 CP= .63 NYA= 0

RECESSION DATA

STRTO= -1.50 ORCSH= -.05 RTION= 2.00

UNIT HYDROGRAPH 53 END-OF-PERIOD ORDINATES, LAG= 9.66 HOURS, CP= .63 VOL= 1.00

97.	340.	727.	1149.	1404.	2070.	2481.	2705.	2975.	3049.
2970.	2731.	2439.	2170.	1945.	1737.	1551.	1385.	1237.	1105.
987.	881.	787.	703.	627.	560.	500.	447.	399.	356.
310.	284.	254.	227.	202.	181.	161.	144.	129.	115.
103.	92.	82.	73.	65.	58.	52.	47.	42.	37.
33.	30.	26.							

0

END-OF-PERIOD FLOW

NO.DA	HR.HN	PERIOD	RAIN	EXCS	LOSS	COMP O	NO.DA	HR.HN	PERIOD	RAIN	EXCS	LOSS	COMP O
-------	-------	--------	------	------	------	--------	-------	-------	--------	------	------	------	--------

SUM 24.29 21.79 2.51 1014421.
(617.)(533.)(44.)(20725.20)

HYDROGRAPH ROUTING

GREEN LANE OUTFLOW HYDROGRAPH

ISTAG	ICOMP	IECON	ITAPE	JPLT	JPRI	INAME	ISTAGE	IAUTO
GLC	1	0	0	0	0	1	0	0

ROUTING DATA

CLOSS	CLOSS	AVG	IRCS	ISAME	IBP1	IPHP	LSIR
0.0	0.000	0.00	1	1	0	0	0

NSTPS	NSTDL	LAG	ANSKK	ISK	STORA	ISPRAT
1	0	0	0.000	0.000	-286.	-1

STAGE	286.00	287.00	288.00	289.00	290.00	291.00	292.00	293.00	294.00	295.00
	296.00	297.00	298.00	299.00						

FLOW	0.00	1272.00	3772.00	7404.00	11397.00	14496.00	22189.00	28582.00	35598.00	43273.00
	51402.00	40323.00	49622.00	79500.00						

CAPACITY=	34.	321.	1096.	2467.	4784.	9119.	13398.	16942.	20616.
-----------	-----	------	-------	-------	-------	-------	--------	--------	--------

ELEVATION=	230.	240.	250.	260.	270.	280.	286.	290.	300.
------------	------	------	------	------	------	------	------	------	------

CREL	SPHID	COBW	EXPB	ELEVL	COOL	CAREA	EXPL
286.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0

DAM DATA

TOPEL	COBD	EXPB	DAMWID
297.0	3.1	1.5	340.

PEAK OUTFLOW IS 20205. AT TIME 51.00 HOURS

PEAK OUTFLOW IS 25547. AT TIME 51.00 HOURS

PEAK OUTFLOW IS 52690. AT TIME 50.00 HOURS

Green Lane Dam and storage
data obtained from Phase I
Inspection Report

SUB-AREA RUNOFF COMPUTATION

DEEP CREEK INFLOW HYDROGRAPH

ISTAU	ICOMP	IECON	ITAPE	JPLT	JPRT	INAME	ISTAGE	IAUTO
IN	0	0	0	0	0	1	0	0

HYDROGRAPH DATA									
INYDS	IUNG	IAREA	SNAP	TRSDA	TRSPC	RATIO	ISUM	ISARE	LOCAL
1	1	5.62	0.00	95.00	0.00	0.000	0	1	0

PRECIP DATA								
SPFE	PNS	R6	R12	R24	R48	R72	R96	
0.00	23.00	90.00	99.00	109.00	122.00	0.00	0.00	

TRSPC COMPUTED BY THE PROGRAM IS .004

LOSS DATA										
LROPT	STKR	DLTKR	RIIDL	ERADR	STRKS	RIOR	STRIL	CNSTL	ALSMX	RTIMP
0	0.00	0.00	1.00	0.00	0.00	1.00	1.00	.05	0.00	0.00

UNIT HYDROGRAPH DATA
 TP= 3.77 CP= .63 RTA= 0

RECESSION DATA
 STRIO= -1.50 ORCSN= -.05 RIOR= 2.00

UNIT HYDROGRAPH 21 END-OF-PERIOD ORIGINATES. LAG= 1.75 HOURS, CP= .63 VOL= 1.00

73.	261.	474.	596.	555.	426.	317.	236.	176.	131.
97.	72.	54.	40.	30.	22.	17.	12.	9.	7.
5.									

END-OF-PERIOD FLOW													
NO.DA	HR.MM	PERIOD	RAIN	EXCS	LOSS	COMP	NO.DA	HR.MM	PERIOD	RAIN	EXCS	LOSS	COMP

SUN 24.29 21.79 2.51 03924.
 (617.) (553.) (64.) (2376.75)

HYDROGRAPH ROUTING

DEEP CREEK OUTFLOW HYDROGRAPH

ISTAU	ICOMP	IECON	ITAPE	JPLT	JPRT	INAME	ISTAGE	IAUTO
OUT	1	0	0	0	0	1	0	0

ROUTING DATA								
GLSS	CLOSS	AVG	IRIS	ISARE	LOPT	IPMP	LSTR	
0.0	0.000	0.00	1	1	0	0	0	

NSTPS	NSTDL	LAG	ANSEK	I	ISK	STORA	ISPRAT
1	0	0	0.000	0.000	0.000	-225.	-1

STAGE	224.50	225.50	226.50	227.50	228.50	229.50	230.50	232.50
FLOW	0.00	207.00	860.00	1650.00	2622.00	3778.00	5045.00	8187.00

SURFACE AREA=	0.	5.	14.	25.	99.			
CAPACITY=	0.	10.	55.	141.	1039.			
ELEVATION=	210.	215.	220.	225.	240.			

CREL	SPMID	COON	EXPM	ELEV	COOL	CAREA	EXPL
224.5	0.0	0.0	0.0	0.0	0.0	0.0	0.0

DAM DATA			
TOPEL	COOP	EXPD	DAMID
228.0	0.0	0.0	0.

Deep Creek Dam data obtained
 from Phase I Inspection
 Report

CREST LENGTH AT OR BELOW ELEVATION	0.	85.	330.	640.
	228.0	229.0	229.5	230.0

PEAK OUTFLOW IS 3404. AT TIME 40.00 HOURS

PEAK OUTFLOW IS 4343. AT TIME 44.00 HOURS

PEAK OUTFLOW IS 8714. AT TIME 48.00 HOURS

SUB-AREA RUNOFF COMPUTATION

MADDOY CREEK INFLUX

ISTAB ICOMP IECON ITAPE JPLT JPRT INAME ISTATE IAUTO
MCI 0 0 0 0 0 0 1 0 0

HYDROGRAPH DATA

INYB IUNG FAREA SNAP TRSDA TRSPC RATIO ISHOW ISAME LOCAL
1 1 17.93 0.00 95.00 0.00 0.000 0 1 0

PRECIP DATA

SPFE PHS R6 R12 R24 R48 R72 R96
0.00 23.00 90.00 99.00 109.00 122.00 0.00 0.00

TRSPC COMPUTED BY THE PROGRAM IS .666

LOSS DATA

LROPT STNKR DLTKR RTIOL ERAIN STRKS RTIOK STRTL CNSTL ALSHI RTIMP
0 0.00 0.00 1.00 0.00 0.00 1.00 1.00 .05 0.00 0.00

UNIT HYDROGRAPH DATA

TP= 6.27 CP= .63 NTA= 0

RECESSION DATA

STRTO= -1.50 ORCSN= -.05 RTIOR= 2.00

UNIT HYDROGRAPH 34 END-OF-PERIOD ORIGINATES, LAG= 6.25 HOURS, CP= .63 VOL= 1.00

67.	247.	490.	756.	988.	1131.	1171.	1080.	915.	746.
642.	538.	450.	377.	316.	245.	222.	186.	136.	130.
109.	91.	77.	64.	54.	45.	38.	32.	26.	22.
19.	16.	13.	11.						

END-OF-PERIOD FLOW

NO.DA	HR.MM	PERIOD	RAIN	EXCS	LOSS	COMP 0	NO.DA	HR.MM	PERIOD	RAIN	EXCS	LOSS	COMP 0
-------	-------	--------	------	------	------	--------	-------	-------	--------	------	------	------	--------

SUN 24.29 21.79 2.51 240079.
(617.)(553.)(44.)(7387.27)

HYDROGRAPH ROUTING

KNIGHT DAN OUTFLOW HYDROGRAPH

ISTAB ICOMP IECON ITAPE JPLT JPRT INAME ISTATE IAUTO
KNOUT 1 0 0 0 0 0 1 0 0

ROUTING DATA

GLOSS CLOSS AVG IRES ISAME IOPT IPMP LSTR
0.0 0.000 0.00 1 1 0 0 0

NSTPS NSTBL LAG ANSKE I TSK STORA ISPRAT
1 0 0 0.000 0.000 0.000 -213. -1

STAGE	213.00	214.00	215.00	216.00	217.00	218.00	220.00	222.00	225.00
FLOW	0.00	1369.00	4059.00	7712.00	12234.00	17448.00	30449.00	46162.00	71753.00

SURFACE AREA= 0. 7. 19. 34. 42. 78. 85.

CAPACITY= 0. 4. 66. 170. 361. 479. 884.

ELEVATION= 202. 204. 209. 213. 218. 220. 225.

CREL SPUID COMU EXPW ELEV COUL CAREA EXPL
213.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0

DAN DATA

TOPEL COOD EXPD DANVID
220.0 0.0 0.0 0.

CREST LENGTH 100. 150. 160.
AT OR BELOW
ELEVATION 220.0 220.7 225.0

PEAK OUTFLOW IS 25715. AT TIME 50.00 HOURS

PEAK OUTFLOW IS 32586. AT TIME 50.00 HOURS

PEAK OUTFLOW IS 48139. AT TIME 49.00 HOURS

PEAK FLOW AND STORAGE (END OF PERIOD) SUMMARY FOR MULTIPLE PLAN-RATIO ECONOMIC COMPUTATIONS
 FLOWS IN CUBIC FEET PER SECOND (CUBIC METERS PER SECOND)
 AREA IN SQUARE MILES (SQUARE KILOMETERS)

OPERATION	STATION	AREA	PLAN	RATIOS APPLIED TO FLOWS			
				RATIO 1 .40	RATIO 2 .50	RATIO 3 1.00	
HYDROGRAPH AT	GLIN	71.00 (183.89)	1	22229.	27787.	53573.	Green Lane Dam
				(629.47)	(786.83)	(1573.67)	
ROUTED TO	GLO	71.00 (183.89)	1	20205.	25547.	52698.	
				(572.14)	(723.41)	(1492.25)	
HYDROGRAPH AT	IN	5.62 (14.56)	1	3529.	4411.	8823.	Deep Creek Dam
				(99.93)	(124.92)	(249.84)	
ROUTED TO	OUT	5.62 (14.56)	1	3484.	4343.	8714.	
				(98.66)	(122.99)	(246.75)	
HYDROGRAPH AT	HCI	17.93 (46.44)	1	7871.	9829.	19678.	Macoby Creek
				(222.89)	(278.61)	(557.22)	
3 COMBINED	KIN	94.35 (244.88)	1	25774.	32614.	68125.	Knight Dam
				(729.85)	(923.52)	(1929.08)	
ROUTED TO	KNOT	94.35 (244.88)	1	25745.	32584.	68139.	
				(729.83)	(922.73)	(1929.49)	

SUMMARY OF DAM SAFETY ANALYSIS

Green Lane Dam

	INITIAL VALUE	SPILLWAY CREST	TOP OF DAM
ELEVATION	286.00	286.00	297.00
STORAGE	13398.	13398.	25114.
OUTFLOW	0.	0.	60323.

RATIO OF PMF	MAXIMUM RESERVOIR U.S.ELEV	MAXIMUM DEPTH OVER DAM	MAXIMUM STORAGE AC-FT	MAXIMUM OUTFLOW CFS	DURATION OVER TOP HOURS	TIME OF MAX OUTFLOW HOURS	TIME OF FAILURE HOURS
.40	291.65	0.00	18870.	20205.	0.00	51.00	0.00
.50	292.53	0.00	19896.	25547.	0.00	51.00	0.00
1.00	296.14	0.00	24107.	52698.	0.00	50.00	0.00

SUMMARY OF DAM SAFETY ANALYSIS

Deep Creek Dam

	INITIAL VALUE	SPILLWAY CREST	TOP OF DAM
ELEVATION	224.50	224.50	228.00
STORAGE	141.	141.	250.
OUTFLOW	0.	0.	2136.

RATIO OF PMF	MAXIMUM RESERVOIR U.S.ELEV	MAXIMUM DEPTH OVER DAM	MAXIMUM STORAGE AC-FT	MAXIMUM OUTFLOW CFS	DURATION OVER TOP HOURS	TIME OF MAX OUTFLOW HOURS	TIME OF FAILURE HOURS
.40	229.13	1.13	294.	3484.	5.00	44.00	0.00
.50	229.59	1.59	314.	4343.	7.00	44.00	0.00
1.00	230.74	2.74	368.	8714.	11.00	43.00	0.00

SUMMARY OF DAM SAFETY ANALYSIS

Knight Dam

	INITIAL VALUE	SPILLWAY CREST	TOP OF DAM
ELEVATION	213.00	213.00	220.00
STORAGE	170.	170.	479.
OUTFLOW	0.	0.	30449.

RATIO OF PMF	MAXIMUM RESERVOIR U.S.ELEV	MAXIMUM DEPTH OVER DAM	MAXIMUM STORAGE AC-FT	MAXIMUM OUTFLOW CFS	DURATION OVER TOP HOURS	TIME OF MAX OUTFLOW HOURS	TIME OF FAILURE HOURS
.40	219.27	0.00	427.	25743.	0.00	50.00	0.00
.50	220.27	.27	500.	32584.	5.00	50.00	0.00
1.00	224.13	4.13	813.	68139.	17.00	49.00	0.00

SUMMARY OF DAM SAFETY ANALYSIS
GREEN LAKE DAM

	INITIAL VALUE	SPILLWAY CREST	TOP OF DAM
ELEVATION	284.00	284.00	297.00
STORAGE	13398.	13398.	25114.
OUTFLOW	0.	0.	60323.

RATIO OF PMF	MAXIMUM RESERVOIR U.S.ELEV	MAXIMUM DEPTH OVER DAM	MAXIMUM STORAGE AC-FT	MAXIMUM OUTFLOW CFS	DURATION OVER TOP HOURS	TIME OF MAX OUTFLOW HOURS	TIME OF FAILURE HOURS
.40	291.65	0.00	18870.	20205.	0.00	51.00	0.00
.50	292.53	0.00	19890.	25547.	0.00	51.00	0.00
1.00	296.14	0.00	24107.	52698.	0.00	50.00	0.00

SUMMARY OF DAM SAFETY ANALYSIS

DEEP CREEK DAM- Failure Assumed
Bottom elevation of Breach 213

	INITIAL VALUE	SPILLWAY CREST	TOP OF DAM
ELEVATION	224.50	224.50	228.00
STORAGE	141.	141.	250.
OUTFLOW	0.	0.	2136.

RATIO OF PMF	MAXIMUM RESERVOIR U.S.ELEV	MAXIMUM DEPTH OVER DAM	MAXIMUM STORAGE AC-FT	MAXIMUM OUTFLOW CFS	DURATION OVER TOP HOURS	TIME OF MAX OUTFLOW HOURS	TIME OF FAILURE HOURS
.40	229.13	1.13	294.	3484.	5.00	44.00	0.00
.50	229.58	1.58	314.	9939.	3.36	43.50	43.00
1.00	229.93	1.93	329.	11993.	2.45	41.50	41.00


SUMMARY OF DAM SAFETY ANALYSIS
KNIGHT DAM

	INITIAL VALUE	SPILLWAY CREST	TOP OF DAM
ELEVATION	213.00	213.00	220.00
STORAGE	170.	170.	479.
OUTFLOW	0.	0.	30449.

RATIO OF PMF	MAXIMUM RESERVOIR U.S.ELEV	MAXIMUM DEPTH OVER DAM	MAXIMUM STORAGE AC-FT	MAXIMUM OUTFLOW CFS	DURATION OVER TOP HOURS	TIME OF MAX OUTFLOW HOURS	TIME OF FAILURE HOURS
.40	219.27	0.00	427.	25745.	0.00	50.00	0.00
.50	220.25	.25	499.	32403.	5.00	49.00	0.00
1.00	224.12	4.12	813.	68066.	17.00	49.00	0.00

APPENDIX

E









**HYDROLOGIC MAP
KNIGHT DAM**

NAT. I.D. NO. PA.00395


MONTGOMERY COUNTY

DATA OBTAINED FROM U.S. GEOLOGICAL SURVEY QUAD
SHEET ENTITLED NEWARK, PA.-N.J. SCALE 1:250,000

PLATE 1A




POURED 3-24-60
EL 11.55
EL 11.85 (AVERAGE)





KNIGHT DAM - UPPER PERKIDEN VALLEY PARK
MONTGOMERY COUNTY - PA.

2





NOTE: NUMBERS IN CIRCLES DENOTE SEQUENCE OF POURING






KNIGHT DAM
SPILLWAY SECTION
STA. 2+00 TO STA 2+40
SCALE 1/4"=1'-0"





PROFIL

PLAN



2

BOREHOLE N° 5
Sta - 1+75 CL

BOREHOLE N° 6
Sta 3150 P RCL

BOREHOLE N° 6 A
Sta - 4+0 - 5' RCL

BOREHOLE
Sta - 4

Surface Elev 208.07	00'
7 Moist Brown Sandy Clay/Gravel	
11	
26	40' GWD
28 See Note "A"	77.50
31 Wet Brown Sandy Clay/Gravel	
36	
41	
46	
68 Wet Br Sand? Gravel	90'
94 Wet Br Sand? Gravel	100'
210	120'
Hard Broken Granite (Clay Seams Recovery 34)	
Drilled	165'
Hard Broken Granite (Clay Seams Recovery 24)	
Drilled	190'
See Note "B"	
Hard Broken Granite (Clay Seams Recovery 18)	
Drilled	220'
Note "A"	
Moist Brown Sandy Clay/Gravel	
Note "B"	
Hard Broken Granite (Clay Seams Recovery 10)	

Surface Elev 199.59	00'
84 Wet Brown Sandy Gravel	
184 Small Boulders	
170	
150	
161 See Note "A"	31.50
184 Wet Brown Sandy Gravel	
212 Small Boulders Drilled	
284 Ahead of Casing	
Drilled	80'
Soft Brown Sand Gravel Small Boulders	
Recovery 08	
Drilled	110'
Soft Brown Sand Gravel Small Boulders Recovery 09	
Drilled	130'
Hard Granite Rock With Clay Seams	
Recovery 20	
Drilled	180'
Hard Granite Rock With Clay Seams	
Recovery 24	
Drilled	230'
Note "A"	
Wet Brown Sand Gravel - Small Boulders	

Surface Elev 201.42	00'
2 Wet Br Sand Gravel	
6	20'
9 Wet Br Sand Gravel	
29	
31	50'
28 Wet Br Sand Gravel	14.60'
120	75'
Hard Granite Recovery 40	
Drilled	125'
Hard Granite Recovery 44	
Drilled	175'

Surface Elev	
31 Wet Sand	
11	
11	
19 Wet Sand	
42 Wet Sand	
72	
81	
110	
87 See Note	
84 Compact	
89 Small Gr	
110 Ahead of	
121 See Note	
121 Compact	
136 Small G	
174	
190	
84 See Note	
76 Compact	
94 Small G	
76	
184	
180 See Note	
176 Wet Com	
184 with Sm	
191	
200	
180 See Note	
See Note	
Drilled, Recovery	
Note "A"	
Wet Compact Gravel	

BOREHOLE N° 1
Sta 01218-2' RCL

BOREHOLE N° 2
Sta - 0150-35 LCL

BOREHOLE N° 3
Sta - 1+25 - C1

Surface Elev 218.28	00'
20 Dry Sand Gravel - Rock Part	
31	
56	40'
64	50'
12 See Note "A"	
12 Wet Sand Gravel - Rock Part	
18	
21	90' GWD
24	100'
38 See Note "B"	
46 Wet Sand Gravel - Rock Part	
49	120'
Soft - Hard Compact Sand - Recovery 00	
Drilled	180'
Hard Broken Granite - Clay Seams	
Recovery 21	
Drilled	170'
Hard - Granite (Recovery 30)	
Drilled	220'
Hard - Granite (Recovery 13)	
Drilled	240'
Note "A"	
Dry Sand Gravel - Rock Part	
Note "B"	
Wet Sand Gravel - Rock Part	

Surface Elev 211.55	00'
16 Moist Brown Sandy Clay	
18	
21 Clay	
46	40'
31 See Note "A"	18.50' 55'
Drilled See Note "C"	70'
Hard Granite - Solid Recovery 24	
Drilled	100'
Hard Granite Solid Recovery 22	
Drilled	125'
Hard Granite Solid Recovery 45	
Drilled	170'
Note "A"	
Moist Brown Sandy Clay	
Note "B"	
109 Dry Compact Sand	
Note "C"	
Hard Granite - Broken Recovery 05	

Surface Elev 209.10	00'
11 Moist Brown Silty Clay	
12	
19	40'
19	11.50'
11 See Note "A"	
71 Wet Brown Sand Gravel	
18	
47	90'
56	
71 See Note "B"	41.00'
Drilled See Note "D"	120'
Hard - Sand - Gravel with Pieces of Granite Recovery 07	
Drilled	170'
Hard - Broken Granite Recovery 17	
Drilled	200'
Hard Broken Granite Recovery 33	
Drilled	220'
Hard Solid Granite Recovery 20	
Drilled	240'
Note "A"	
Wet Brown Sand Gravel - Changes at 4.5'	
Note "B"	
Wet Brown Sand Gravel	
Note "C"	
181 Wet Brown Sand Gravel	

BOREHOLE N° 7
Sta. 4+30-CL

BOREHOLE N° 8
Sta. 4+75-10' RCLL

Surface Elev. 209.0 00'

31	Wet Sand & Gravel	00'
11		
9		
13	Wet Sand & Gravel	40'
46	Wet Sand & Gravel	85.0' G.W.D.
72		
81		
110		
97	See Note "A"	9.0'
84	Compact Sand With	31' 100'
89	Small Gravel - Drilled	
110	Ahead of Casing - Wet	
81		
11	See Note "A"	48' 150'
21	Compact Sand With	
136	Small Gravel - Wet	
174		
190		
184	See Note "A"	19.0'
176	Compact Sand With	31' 200'
94	Small Gravel - Wet	
176		
184		
180	See Note "A"	24.0'
176	Wet Compact Sand	58' 250'
184	With Small Gravel	
191		
200		
180	See Note "A"	29.0'
180	See Note "A"	56' 300'
Drilled Recovery 0.6		32.0'

Note "A"
Wet Compact Sand With Small Gravel

Surface Elev. 212.10 00'

31	Wet Brown Clay -	00'
64	Sand & Gravel	
41		
40		
40	See Note "A"	18' 40'
46	Wet Brown Clay -	18' 50'
61	Sand & Gravel	
72		
94		
80	See Note "A"	90' G.W.D.
101	Wet Brown Clay -	46' 100'
164	Sand & Gravel	
182		
190		
219	Wet B. Sand & Gravel	58' 150'
218	Wet Compact Sand	
284	f. Small Gravel	
271		
281		
See Note "B"		61' 190'
		200'

Note "A"
Wet Brown Clay - Sand & Gravel

Note "B"
Wet Compact Sand & Small Gravel

AUGER BORING

Depth	Log of Hole	Depth Drilled
	HOLE #1 Not Drilled - Boulders	
	HOLE #2	
0-2	Dry Brown Sandy Clay	2.0
2-4	Dry Brown Sandy Clay	2.0
4-55	Dry Brown Sandy Clay	1.5
	HOLE #3 Not Drilled - Boulders	
	HOLE #4	
0-2	Dry Light Brown Sandy Clay	2.0
2-3	Dry Light Brown Sandy Clay	1.0
	HOLE #5	
0-2	Dry Light Brown Sandy Clay	2.0
2-4	Dry Light Brown Sandy Clay	2.0
4-6	Dry Light Brown Sandy Clay & Small Gravel	2.0
	HOLE #6	
0-2	Dry Light Brown Sandy Clay	2.0
	HOLE #7	
0-2	Dry Light Brown Sandy Clay	2.0
2-4	Dry Light Brown Sandy Clay	2.0
4-6	Dry Light Brown Sandy Clay	2.0
	HOLE #8	
0-2	Dry Light Brown Sandy Clay	2.0
2-4	Dry Light Brown Sandy Clay	2.0
4-55	Dry Light Brown Sandy Clay	1.5

BOREHOLE N° 3
Sta. 1+25-CL

BOREHOLE N° 4
Sta. 2+0-10' RCLL

Surface Elev. 209.10 00'

11	Moist Brown Silty Clay	00'
11		
11	See Note "A"	40' G.W.D.
11	Wet Brown Sand & Gravel	11' 50'
11		
11		
11	See Note "B"	90'
11		41' 100' 105'
11	See Note "D"	120'
11	Hard Sand & Gravel With Pieces of Gravel Recovery 0.7	
11		
11	Hard Broken Granite Recovery 17	170'
11	Hard Broken Granite Recovery 33	200'
11		
11	Hard Sand & Gravel Recovery 20	250'
11		270'

Note "A"
Brown Sand & Gravel - Changes at 5'

Note "B"
Brown Sand & Gravel

Note "C"
Wet Brown Sand & Gravel

Surface Elev. 208.85 00'

8	Moist Brown Silty Clay	00'
21		
26		
21	See Note "A"	3' 40' G.W.D.
61	Wet Brown Sand & Gravel	3' 50'
72		
84		
30	Wet B. Sand & Gravel	9.0'
110	Wet Sand & Gravel - Thick	61' 100'
110	Drilled Recovery 1.0	
110	Hard Granite Broken & Clay Spans Recovery 4.0	120'
110		
110	Hard Granite Broken & Clay Spans Recovery 2.5	170'
110		
110		220'

Note "A"
Wet Brown Sand & Gravel - Change at 4.5'

TEST PITS

Depth	Log of Hole	Depth Drilled
0-5	TEST PIT #1 - Sta. 0+87-CL Brown Silty Clay	5.0
5-75	Gray Clay - Sand & Small Gravel Water Seepage in Bottom of Hole - 1 Block Sample	2.5
	TEST PIT #2 - Sta. 1+75-CL	
0-4	Brown Silty Clay	4.0
4-6	Brown Sand & Gravel No Sample - Hole Stopped by Inspector Because of too Much Gravel & Water to get Block Sample	2.0
	TEST PIT #3 - Sta. 2+60-CL	
0-2	Brown Silty Clay	2.0
2-65	Brown Sand & Gravel No Sample - Hole Stopped by Inspector Because of too Much Gravel & Water to get Block Sample	4.5
	TEST PIT #4 - Sta. 4+50-CL	
0-76	Brown Sand & Gravel - Trace of Clay Water Seepage in Bottom of Hole - 1 Block Sample	7.6

APPENDIX

F

SITE GEOLOGY
KNIGHT DAM

Knight Dam is located in the Triassic Lowland Section of the Piedmont Physiographic Province. As shown in Plate F-1, the dam is underlain by diabase bedrock of Triassic age which has intruded the Brunswick and Lockatong shale formations. The surrounding region has experienced folding resulting in broad west-northwest trending anticlines and synclines. The dam is situated within an anticline or upfold. Rock jointing observed in bedrock exposures above the right abutment area strike north-northeast and west-northwest having dips generally greater than 70 degrees. The dense diabase bedrock occurs at relatively shallow depths as indicated by the spheroidal boulders common in the area and the exposures present in the Perkiomen Creek.

